



Republic of the Philippines
Province of Surigao del Sur
City of Bislig

INVITATION TO BID

The Local Government Unit of Bislig City, through its Bids and Awards Committee (BAC) invites PhilGEPS registered Supplier's to apply for eligibility and to bid for the hereunder project:

Name of Project : **SUPPLY & DELIVERY OF LED VIDEO WALL**

Location : City Hall Compound, Bislig City

Brief Description : 1 Unit LED VIDEO WALL

Pixel Pitch > P3.5mm – P4.0mm with Video Processor , Sending Card
Ingress Protection: Front IP40, Rear IP21
High Precision and Rigidity
Direct Wall Mounted Design with Complete Accessories
Brightness up to 800-1000 Nits and Refresh rate Up to 1920hz-2000hz
LED Type: SDM2020 (Black)
Size Module 250mm by 250mm
Resolution of Module: 64 by 64
Density: 65000-70000 dots/m
Best Viewing Angle 140 Degrees
Control Method: Synchronization
Working Voltage: 220V AC
Working Temperature: -10 to +40°C
Operating Humidity: 10% to 90%
Module Maintenance: Front / Rear
Power Supply Unit (PSU) & Other Maintenance: Rear
Panel Materials: Die Casting Aluminum
Life Span: 100,000 Hrs (Minimum)

Include:

- A. 1 pc. Sending Card Box
- B. 132 pcs. Receiving Card
- C. 1 pc. LED Video Processor
- D. 1 set LED Software
- E. 1 set Laptop Control Player
 - Processor: Core i7, 2.6GHz or Higher (At least 6M Cache, Up to 3.5GHz)
 - OS: Windows 10
 - Memory: 8GB DDR4 or Latest
 - Display: 17.3 inch; 16:9 Full HD
 - Graphics: 4GB, GDDR5 VRAM
 - Storage: 1TB HDD; Optical Drive; Card Reader Networking; USB Port; HDMI w/ Bag and AVR.

- a. 1 lot Installation of LED Frame, Installation of LED unit and Electrical Requirement including AVR.
- b. Delivery and Mobilization

Structural Works and Restoration Works

- * Structural Design of Framing System for the LED display (Signed and Sealed)
- * Construction of Main Support Framing System for LED Signage to include Vertical, Horizontal
- * Mounting of LED Cabinets
- * Restoration of Affected Areas
- * Supply and Installation of Cladding (Front Only)

Electrical Works

- * Supply and Installation of Power System to Include Panel Board Circuit Breakers, Utility Boxes, Wires and Cable, and Necessary Accessories.
- * Supply and Installation of 2pcs. AVR (10KVA)
- * Supply and Installation of FEEDERLINE (50mtrs)

Signal Cabling System

- * CAT 5 w/ Rough-ins (Approx. 100mtrs)

Approved Budget
For the Contract : Php 8,350,000.00

Source Funds : 20% EDF CY – 2018

Delivery Period : 45 C.D.

Prospective bidders should have experience in undertaking a similar project within the last years of 2016 and 2017 (minimum of 2 years) with an amount of at least 50% of the proposed project for bidding. The Eligibility Check/Screening as well as the Preliminary Examination of Bids shall use non-discretionary “pass/fail” criteria. Post-qualification of the lowest calculated bid shall be conducted.

All particulars relative to Eligibility Statement and Screening, Bid Security, Performance Security, Pre-Bidding Conference, Evaluation of Bids, Post-qualification and Award of Contract shall be governed by the pertinent provisions of R.A. 9184 and its Implementing Rules and Regulation (IRR).

The complete schedule of activities is listed, as follows:

Activities	Schedule
1. Issuance of Bid Documents	June 6 -25, 2018
2. Pre-bid Conference	June 11, 2018
3. Opening of Bids	June 25, 2018
4. Bid Evaluation	June 26-28, 3028
5. Post-qualification	June 29-July 3, 2018
6. Notice of Award	July 6, 2018

Bid Documents will be available only to prospective bidders upon payment of a non-refundable amount of P10,000.00 to the LGU Bislig City Cashier.

The LGU Bislig City assumes no responsibility whatsoever to compensate or indemnify bidders for any expenses incurred in the preparation of the bid.

The BAC of Bislig City reserves the right to accept or reject any bid, to annul the bidding process, and to reject all Bids at any time prior to contract award, without thereby incurring any liability to the affected bidder or bidders.

Approved by:

Dates of Publication: _____
Newspaper: _____

(SGD.) RENEFREDO G. CAMBA, CPA
BAC Chairman